Statement showing the approximate quantities of work for constructing a Silt Reservoir at Sivasamudram.

No.	Items of wrok	Quantity	Unit
	Abstract quantity for constructing the bund—		
1	Foundation excavation and refilling the excavated earth with consolidation ..	2,972	C. yd.
2	Earthwork embankment with consolidation including lead. Different rates for leads from 50′ to 600′ and lifts ranging from 5′ to 30′.	21,005	,,
3	Rough stone revertment	2,816	,,
4	Turfing	345·40	Square
5	Legend stones	No. 1	Each
6	Benchmark stones	No. 2	,,
7	Grade stone	No. 14	,,
8	Index stones	No. 14	,,
	(2) Abstract quantity for constructing the weir—		
1	Concrete foundation stone jelly in surki mortar	2,367	C. ft.
2	Coursed stone in surki mortar	7,344	,,
3	Stone slabs 6″ thick dressed	1,805	S. ft.
4	Stone slabs 6″ thick undressed	472	,,
5	Cement pointing	45·84	Sqr.
6	Rough stone apron set in stone jelly in surki mortar concrete	212	C. yd.
	(3) Abstract quantity for constructing a sluice—		
1	Concrete foundation stone jelly in surki mortar	3,841	C. ft.
2	Course stone in surki mortar	9,373	,,
3	Cut waters 2½′ x 2′ including stone masonry built in surki mortar ..	14	R. ft.
4	Stone slabs 6″ thick	2,442	S. ft.
5	Cement pointing	52·08	Sqr.
6	Sluice shutter with gearing, etc., complete as per design	No. 2	..
	(4) Abstract quantity for raising the road culvert in Maddur Sivasamudram road 25th mile 5th furlong—		
1	Dismantling the road way	17	C. yd.
2	Dismantling parapet wall	312	C. ft.
3	Removing the covering slab	640	Sft.
4	Burnt brick in surki mortar	1,606	C. ft.
5	Resetting old covering slab over tunnel including pointing	640	S. ft.
6	New stone slabs 9″ thick	48	C. ft.
7	Plastering with surki mortar	15 45	Sqr.
	(5) Abstract quantity for raising Maddur-Sivasamudram road for a length of 720. to Road Level 99·800—		
1	Picking, stacking the road metal	2,560	S. yd.
2	Earth-work embankment, lead and lift to be stated	1,424	C. yd.
3	Turfing	64 80	Sqr.
4	Metalling the road surface with 6″ metal at centre including consolidation of metal gravel, etc.	160	C. yd.
	(6) Abstract Estimate for constructing the Nos. 1, 2 and 3 silt traps at Sivasamudram—		
1	Benching rock	200	S. ft.
2	Coursed stone in surki mortar	385	C. ft.
3	Stone slabs 6″ thick dressed	200	S. ft.
4	Cement pointing	5·85	Sqr.

C. R. WOODCOCK,
General Superintendent.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE SUPERINTENDENT, MYSORE CIVIL VETERINARY DEPARTMENT, BANGALORE CITY.

Notice No. 913, *dated 25th July* 1924.

Tenders are invited up to the 31st August 1924, for the supply of 100 cwts. of Epsom salts, superior quality, to be delivered to the undersigned in barrels of 1 cwt. by the end of 31st October 1924.

R. W. SIMPSON, MAJOR,
Superintendent,
Mysore Civil Veterinary, Department.